
	Model (Triplex)	0-3 PPM	3-8 PPM	8-15 PPM	Max Flow To Drain	Pipe Size		Media	Mineral Tank		Installation			Shipping Weight	Operating Weight
		Max System Flow Rate			Diam	Service	Drain	Per Tank	Diameter	Height	Height	Depth	Width	Weight	Weight.
		USGPM	USGPM	USGPM	USGPM	in	in	CF	in	in	in	in	in	lbs	lbs
		I/s	I/s	I/s	I/s	mm	mm	m3	mm	mm	mm	mm	mm	kg	kg
	95MTS	15	9	6	11	1.25"	1"	2.75	14	65	79	20	60	1,194	2,394
	MG14-1.25"	0.96	0.57	0.39	0.69	32	25	0.078	356	1651	2006.6	508	1524	542	1,086
	95MTS	21	12	7.5	14	1.25"	1"	3.5	16	65	79	22	66	1,501	3,001
	MG16-1.25"	1.32	0.75	0.48	0.88	32	25	0.1	406	1651	2006.6	559	1677	681	1,362
	95MTS	27	15	10.5	17	1.25"	1"	4.4	18	65	79	24	72	1,800	3,600
	MG18-1.25"	1.68	0.96	0.66	1.07	32	25	0.125	475	1651	2006.6	610	1830	817	1,633
	95MTS	36	21	15	24	1.25"	1"	6	21	62	77	27	81	2,447	4,847
	MG21-1.25"	2.28	1.32	0.96	1.51	32	25	0.17	533	1575	1956	686	2058	1,110	2,199



## NOTES

- TRIPLEX FILTER, CALENDAR CLOCK INITIATED, MULTI-TANK SYSTEMS ARE SERIES REGENERATION.
- FILTER IS EQUIPPED WITH 1.25" VALVE ELECTRONIC BALL VALVE WITH MAIN ELECTRONIC CONTROLLER.
- MAXIMUM RECOMMENDED SYSTEM PRESSURE IS 100 PSI (690 kPa) AND MINIMUM INLET PRESSURE IS 40 PSI.
- MAXIMUM RECOMMENDED SYSTEM TEMPERATURE IS 100 °F (38 °C).
- REQUIRES 120 VOLT, 1 PHASE, 60 Hz ELECTRICAL POWER.
- ALL EXTERNAL PIPING, FITTINGS, AND VALVES SHOWN BY BROKEN LINES ARE SUPPLIED BY OTHERS.
- MINERAL TANKS AND MEDIA ARE NSF APPROVED.
- DUE TO SLIGHT EXPANSION AND CONTRACTION OF MINERAL TANK, PIPING MUST BE DESIGNED TO ALLOW SOME MOVEMENT. AS WELL AS BE PROTECTED FROM VACUUM. FLEX CONNECTORS AND A VACUUM BREAKER MAY BE REQUIRED. FAILURE TO INSTALL EITHER OF THEM OR IMPROPERLY INSTALL THEM MAY VOID THE WARRANTY.
- FLOOR DRAINS MUST BE SIZED TO CARRY THE MAX. LISTED FLOW TO DRAIN.
- REFER TO THE INSTALLATION AND OPERATION MANUAL FOR FURTHER DETAILS
- USE PROPER UNION OR FLANGE FOR THE PIPE CONNECTION TO VALVE FOR EASY MAINTENANCE.
- SYSTEM MUST BE INSTALLED TO COMPLY WITH ALL FEDERAL, STATE, PROVINCIAL, & LOCAL CODES, MEDIA BED CONSISTS OF, NSF APPROVED MEDIA CONSISTS OF (FROM TOP TO BOTTOM)
- ANTHRACITE, MANGANESE GREENSAND ON A GRADED SUPPORT BED
- SYSTEM IS SUPPLIED WITH A GRADUATED CHEMICAL TANK AND STANDARD CONTINUOUS FEED CHEMICAL PUMP, (NOT SHOWN). IF THE SYSTEM HAS VARYING FLOW RATES, AN OPTIONAL FLOW

PACED CHEM FEED SYSTEM MUST BE USED.



UNION OR FLANGE

## 95MTS GREENSAND FILTER 1.25" TRIPLEX SYSTEM

THIS DOCUMENT CONTAINS INFORMATION WHICH IS PROPRIETARY TO CANATURE WATERGROUP. THE REPRODUCTION, TRANSFER, OR OTHER EXPLOITATION OF ANY INFORMATION CONTAINED HEREIN IS NOT PERMITTED WITHOUT PRIOR WRITTEN APPROVAL OF CANATURE WATERGROUP. THE MANUFACTURER RESERVES THE RIGHT TO MAKE PRODUCT REVISIONS, WHICH MAY DEVIATE FROM THE SPECIFICATIONS AND DESCRIPTIONS STATED

•	HEREIN WITHOUT OBLIGATION TO CHANGE P PRODUCTS OR TO NOTE THE CHANGE.	REVIOUSLY MANUFACTURED	
C	Project	Date 10-18-2017	Rev
on		Dwg # 95MTS MG1.25T	0